# 4ELEMENTS PAINTING
PTY LTD

# QUOTE

Quote No: QT-0035
Date: 26/08/2026
Valid Until: 08/09/2026

## CLIENT

**Client Name: Eric CHONG**
**Client Address: 15 Yarrabung Ave, Thornleigh, NSW, 2120**
**Phone: 0403 019 717**
**Email: ews_chong@yahoo.com.au**

## PREPARED BY

**4Elements Painting**
**Address: Bolwarra Heights, NSW, 2320**
**Phone: 0421 216 949**
**Email: info@4elementspainting.com.au**
**ABN: 37282947279**

## JOB DESCRIPTION

### External Eaves & Brick Painting

Supply all materials and professionally prepare and repaint the nominated external eaves and brick surfaces. Areas showing signs of mould will be properly treated and prepared, with suitable anti-mould primer/undercoat applied where required, followed by premium exterior top coats for a clean, durable and weather-resistant finish.

| QUOTE TOTAL |
|---|
| $ 13500<br>(GST Inclusive) |

## WORK PROCESS

| STEP | PROCESS | DESCRIPTION | Estimated working Days |
|---|---|---|---|
| 1 | **Prepare & Protect** | Protect windows, doors, floors and surrounding surfaces. Clean and prepare all nominated areas before painting. | 8 |
| 2 | **Mould Treatment & Preparation** | Treat and clean visible mould-affected areas. Remove loose/flaking material and prepare surfaces as required. | |
| 3 | **Eves - Prime** | Apply a full coat of suitable anti-mould primer/undercoat to the nominated eaves and finish with two top coats of external premium paint. | |
| 5 | **Brickwork - Spot Prime** | Spot-prime prepared areas of brickwork where required, including areas previously affected by mould or showing signs of surface deterioration. | |
| 6 | **Brickwork - Top Coats** | Apply 2 coats of premium exterior paint to the nominated brick surfaces for an even and weather-resistant finish. | |
| 7 | **Final Inspection & Clean Up** | Complete final touch-ups, remove masking/protection and leave the work area clean and tidy. | |

**Note: All work will be carried out in accordance with industry best practices and weather conditions permitting.**

## SITE PHOTOS

## INCLUSIONS

- Labour and equipment
- Surface preparation as outlined above
- Application of 2 coats finish paint
- Site clean up

## EXCLUSIONS

- Any repairs to damaged timber
- Additional coats beyond scope

## TERMS & CONDITIONS

- This quote is valid for 14 days from the date above.
- Payment terms: 20% deposit, balance on completion unless otherwise agreed.
- Any additional work outside the scope will be quoted separately.
- We are fully insured for public liability.